

Date: 01/28/2016

TOWN OF ISLESBORO
P.O BOX 76
ISLESBORO, Maine 04848

RE: Application number A-2015-1400
Licensee reference number: ISLESBORO04

Dear Cristin Turner:

Enclosed, please find Form 4, Authorization for Pole Make-Ready Work.

Please sign this form and return it with your check made payable to **FairPoint Communications** in the amount of **\$21,472.50**. This amount due is for the Make-Ready Work associated with the application number referenced above in the vicinity of Main Rd, Meadow Pond Rd, Islesboro, ME.

Please note: If payment is not received by 02/27/2016 the application will be canceled and you will need to reapply.

Please call 1-866-774-5228 to speak with a License Administration Associate should you have any questions.

Please submit payment to:

**Fairpoint Communications
License Administration Group
5 Davis Farm Rd
Portland, ME 04103**

Sincerely,

Cathleen Adams
License Administration

Attachments

AUTHORIZATION FOR POLE MAKE-READY WORKLicensee: **Town of Islesboro**

Field survey work associated with your License Application No. **Islesboro 04** dated **November 17, 2015**
 for attachments to poles in the municipality of **Islesboro**, State of **ME** has been completed.
 Following is a summary of the make-ready charges which will apply:

TASK #	QUANTITY	UNIT COST	TOTAL COST
7A	9	\$227.70	\$2,049.30
7B	1	\$110.00	\$110.00
10A	7	\$218.90	\$1,532.30
10B	1	\$102.30	\$102.30
11A	20	\$258.50	\$5,170.00
11B	4	\$85.80	\$343.20
19A	22	\$157.30	\$3,460.60
19B	14	\$35.20	\$492.80
Work Order Preparation			\$165.00
Additional charge Sheet 2			\$8,047.00

Attached as requested, is an itemized unit cost (Form 3) of required make-ready work and associated charges. If you wish us to complete the required make-ready work, please sign this copy below and return with an advance payment in the amount of **\$21,472.50**

Licensors Name (Print) **FAIRPOINT**

Signature ***William R Redman***

Title **Outside Plant Engineer**

Address **5 Davis Farm Rd
Portland, ME 04103**

Telephone Number **207-951-6949**

Date **January 28, 2016**

The replacements and rearrangements included in Pole Attachment License Application No. **Islesboro 04** are authorized and the costs therefore will be paid to Licensors in accordance with Appendix I to Pole Attachment License Agreement. My check is attached.

Licensee's Name (Print) _____

Signature _____

Telephone Number _____

Title _____

Date _____

TASK #	QUANTITY	UNIT COST	TOTAL COST
20A	5	\$156.20	\$781.00
21A	10	\$152.90	\$1,529.00
25A	9	\$210.10	\$1,890.90
26	4	\$256.00	\$1,024.00
17A	9	\$157.30	\$1,415.70
17B	12	\$35.20	\$422.40
18A	2	\$156.20	\$312.40
18B	3	\$35.20	\$105.60
21B	2	\$33.00	\$66.00
30	1	\$500.00	\$500.00

TASK #30 Ferry Tolls for crew and equipment

FORM 3 - FAIRPOINT ITEMIZED POLE MAKE-READY WORK CHARGES

Appendix IV Form 3

FIELD SURVEY / MAKE READY WORK FORM														
RCE to Complete - Total Poles Surveyed			200		Total Poles Requiring Make Ready			Fairpoint		53 Others		48		
Surveyors:			Survey Date:		12/03/15		Survey Order #		ME A20151521APP					
Fairpoint Bill Redman			Munic:		Islesboro		State:		Maine		Exch Code: 7283 Munic Code: 7283901			
Licensee			Licensee Name:		Town of Islesboro		Licensee Application #		Islesboro 04					
Elco Elmer Plummer			Elco Name:		Central Maine Power		LAG Application #		A-2015-1521		days			
Location			Pole #		Attach		Ownership							
Tel Rte / Street Name	Tel	El	F/C PS	J.O. Tel	J.U. El	S.O. Tel	S.O. El	Description of Work	FP	Others	Tasks	Attach location see notes		
RP954 / Main Rd off Rte 95 P10	1/2	250	F		X			Tel lower 1 strand(1 ca) 6".	X		11A	*		
RP954 / Rebel Hill Rd	1	1	F		X			No make ready required.				*		
RP954 / Rebel Hill Rd	2	2	F		X			CMP rpl 35'/40' & 2 anchors. Tel transfer 2 strands(2 ca), 2 PA guys, 3 d/w. NO CHARGE. Noncompliant clearances. Tel 12" from transformer. Guying required.	X	X		*		
RP954 / Rebel Hill Rd	2-1	2.1	F		X			Tel lower 1 d/w 12".	X		19A	*		
RP954 / Rebel Hill Rd	3	3	F		X			No make ready required. Guying required.				*		
RP954 / Rebel Hill Rd	4	4	F		X			No make ready required. Guying required.				*		
RP954 / Rebel Hill Rd	5	5	F		X			No make ready required. Guying required.				*		
RP954 / Rebel Hill Rd	NT	5.1						Customer owned meter pole.				*		
RP9541 / off Rebel Hill Rd RP954 P.4	1	1	F		X			No make ready required. Guying required.				*		
RP9541 / off Rebel Hill Rd RP954 P.4	2	2	F		X			No make ready required. Guying required.				*		
RP9541 / off Rebel Hill Rd RP954 P.4	3	3	F		X			No make ready required. Guying required.				*		
Rte 95 / Main Rd	NT	251	F				X	No Tel on pole. No make ready required.				*		
Rte 95 / Main Rd	10	250S	F		X			Tel raise 2 strands(3 ca) 12", rpl 1 PA guy. Guying required.	X		7A,11A,11B,25A	*		

Location			Pole #	Attach	Ownership						Description of Work		FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.								
				Tel	El	Tel	El	Tel	El							
Rte 95 / Main Rd	9S	249	F					X			No make ready required. Guying required.					*
Rte 95 / Main Rd	9	NT	F						X		No make ready required. No CMP.					*
Rte 95 / Main Rd	NT	248	F							X	No Tel on pole. No make ready required.					*
Rte 953 / Hewe's Point Rd off Rte 95 P.9	1	1	F						X		Tel lower 1 strand(1 ca), 1 PA guy 12"	X			10A,11A	*
	2	2	F						X		CMP rpl 35'/40'. Tel transfer 1 strand(1 ca), 1 terminal, 2 d/w, 1 PP guy.	X	X		10A,11A,14A,17A, 17B	*
Rte 953 / Hewe's Point Rd	2S	2S	F						X		No make ready required. Guying required.					*
Rte 953 / Hewe's Point Rd	3	3	F						X		No make ready required.					*
Rte 953 / Hewe's Point Rd	4	4	F						X		No make ready required.					*
Rte 953 / Hewe's Point Rd	5	5	F						X		CMP rpl 30'/40'. Tel transfer 1 strand(1 ca), 1 d/w. NO CHARGE. Noncompliant clearances. Tel 14'3" over driveway.	X	X			*
Rte 953 / Hewe's Point Rd	NT	5S								X	No Tel on pole. No make ready required. Guying required.					*
Rte 953 / Hewe's Point Rd	6	6	F						X		CMP rpl 35'/40'. Tel transfer 1 strand(1 ca), 1 d/w.	X	X		11A,17A	*
Rte 953 / Hewe's Point Rd	NT	2									Private meter pole. Maddie Dodge Field.					*
Rte 953 / Hewe's Point Rd	7	7	F						X		No make ready required.					*
Rte 953 / Hewe's Point Rd	UNK	7.5									No pole found.					*
Rte 953 / Hewe's Point Rd	7-1	7.1	F						X		CMP raise 2 services 18" & shorten taps. No tel make ready required.		X			*
Rte 953 / Hewe's Point Rd	NT	7S								X	No Tel on pole. No make ready required.					*
Rte 953 / Hewe's Point Rd	8	8	F						X		No make ready required.					*
Rte 953 / Hewe's Point Rd	8-1	8.1	F						X		Tel lower 1 d/w, 1 wire term 12". Guying required.	X			19A,21A	*
Rte 953 / Hewe's Point Rd	UNK	UNK									No pole found.					*

Location			Pole #	Attach	Ownership						Description of Work			FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks	Attach location see notes			
				Tel	El	Tel	El	Tel	El								
Rte 953 / Hewe's Point Rd	10	10	F				X			CMP raise takeoff neutral to main neutral. Tel lower 2 d/w 6". Guying required.	X	X	19A,19B	*			
Rte 9535 / off Hewe's Point Rd Rte 953 P.10	1	10.1	F				X			No make ready required.				*			
Rte 9535 / off Hewe's Point Rd	2	10.2	F				X			No make ready required. Guying required.				*			
Rte 9535 / off Hewe's Point Rd	3	10.3	F				X			CMP raise service 12" & shorten taps. No Tel make ready required.		X		*			
Rte 953 / Hewe's Point Rd	NT	10S							X	No Tel on pole. No make ready required.				*			
Rte 953 / Hewe's Point Rd	11	11	F				X			Tel lower 1 strand(1 ca), 2 d/w 12" .	X		11A,19A,19B	*			
Rte 953 / Hewe's Point Rd	12	12	F				X			Tel raise 1 strand(1 ca), 2 d/w 12"	X		11A,19A,19B	*			
Rte 953 / Hewe's Point Rd	12-1	12.1	F				X			No make ready required.				*			
Rte 953 / Hewe's Point Rd	13	13	F				X			No make ready required. Guying required.				*			
Rte 953 / Hewe's Point Rd	14	14	F				X			No make ready required. Guying required.				*			
Rte 953 / Hewe's Point Rd	16	16	F				X			CMP rpl 35'/40' & anchor. Tel transfer 1 strand(1 ca), 2 d/w, rpl 1 PA guy. Guying required.	X	X	7A,11A,17A,17B,25A	*			
Rte 953 / Hewe's Point Rd	16D	16.1	F				X			Tel lower 1 d/w, 1 wire term 12"	X		19A,21A	*			
Rte 953 / Hewe's Point Rd	17	17	F				X			CMP remove 3 wire rack, raise 1 service 12" & shorten taps. No tel make ready required.		X		*			
Rte 953 / Hewe's Point Rd	18	18	F				X			CMP shorten service taps. No tel make ready required. Guying required.		X		*			
Rte 953 / Hewe's Point Rd	19	19	F				X			CMP rpl 35'/40' & anchor. Tel transfer 1 strand(1 ca), 6 d/w, 1 mdw, rpl 1 PA guy. Guying required.	X	X	7A,11A,17A,(6)17B, 25A	*			
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	19-1	19.1	F				X			CMP raise 2 services 12" & shorten taps. No tel make ready required. Guying required.		X		*			
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	19-2	19.2	F				X			CMP raise 1 service 12" & shorten taps. No tel make ready required. Guying required.		X		*			
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	NT	19.3								CMP transformer pad.				*			

Location		Pole #	Attach		Ownership								Description of Work			FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks	Attach location see notes					
				Tel	El	Tel	El	Tel	El										
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	NT	19.4								CMP transformer pad.				*					
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	NT	19.41								CMP transformer pad.				*					
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	NT	19.5								CMP transformer pad.				*					
Rte 953 / Abrams Mtn Rd off Hewe's Point Rd	NT	19.6								CMP transformer pad.				*					
Rte 953 / Hewe's Point Rd	20	20	F						X	No make ready required. Guying required.				*					
Rte 953 / Hewe's Point Rd	21	21	F						X	No make ready required. Guying required.				*					
Rte 953 / Hewe's Point Rd	23	23	F						X	No make ready required.				*					
Rte 953 / Hewe's Point Rd	23-1	23.1	F						X	No make ready required.				*					
Rte 953 / Hewe's Point Rd	24	24	F						X	No make ready required. Guying required.				*					
Rte 953 / Hewe's Point Rd	25	25	F						X	CMP rpl 35'/40'. Tel transfer 5 d/w, 2 wire terms.	X	X	17A,(4)17B,21A,21B	*					
Rte 953 / Hewe's Point Rd	26	26	F						X	No make ready required.				*					
Rte 953 / Hewe's Point Rd	27	27	F						X	No make ready required. Guying required.				*					
Rte 95 / Main Rd	8	NT	F							No make ready required. Guying required. No CMP on pole.				*					
Rte 95 / Main Rd	7	247	F						X	CMP raise neutral 12". No tel make ready required. Guying required.		X		*					
Rte 95 / Main Rd	6	244	F						X	CMP raise service to neutral & shorten taps. No tel make ready required.		X		*					
Rte 95 / Main Rd	5	243	F						X	No make ready required.				*					
Rte 95 / Main Rd	5-1	243.1	F						X	No make ready required.				*					
Rte 95 / Main Rd	4	242	F						X	CMP raise service 12" & shorten taps. No Tel make ready required.		X		*					
Rte 95 / Main Rd	3	241	F						X	Tel lower 1 strand(2 ca) 12" .	X		11A	*					
Rte 95 / Main Rd	2	240	F						X	CMP raise 2 services 12" & shorten taps. No tel make ready required.		X		*					

Location			Pole #	Attach	Ownership										Tasks			Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks					
				Tel	El	Tel	El	Tel	El									
Rte 95 / Main Rd	NT	239.1	F							No Tel on pole. No make ready required.				*				
Rte 95 / Main Rd	1	239	F				X			CMP shorten service taps. No tel make ready required. Guying required.		X		*				
TS264 / Main Rd	563	238	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	562	98	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	561	97	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	561-1	97.1	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	560	96	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	559	95	F				X			No make ready required.				*				
TS264 / West Bay Rd	558	94	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	557	93	F				X			CMP shorten secondary taps. No tel make ready required.		X		*				
TS264 / West Bay Rd	556	92	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	555	91	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	554	90	F				X			Tel lower 1 strand(2 ca) 12" .	X		11A	*				
TS264 / West Bay Rd	553	89	F				X			CMP rpl 35'/45' & anchor. Tel transfer 1 strand(2 ca), 2 d/w, rpl 1 PA guy. Guying required. NO CHARGE. Noncompliant 14' road clearance.	X	X		*				
TS264 / Utgoff Ln off West Bay Rd	552D	88.1	F				X			No make ready required.				*				
TS264 / West Bay Rd	552	88	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	551	87	F				X			No make ready required. Guying required.				*				
TS264 / West Bay Rd	NT	87.1	F						X	No Tel on pole. No make ready required.				*				
TS264 / West Bay Rd	550	86	F				X			CMP raise 1 service 12" & shorten taps. No tel make ready required. Guying required.		X		*				

Location			Pole #		Attach		Ownership						Description of Work	FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.	J.U.	S.O.											
				Tel	El	Tel	El	Tel	El	Tel	El						
Rte 947 / Smith's Landing Rd	1	86.1	F				X						CMP place 18" U-guard on URD, replace anchor & refension primary & neutral. Tel refension 1 strand(1 ca), 1 mdw P.1-2, rpl 1 PA guy. NO CHARGE. Guying required.	X	X		*
Rte 947 / Smith's Landing Rd	2	86.11	F				X						No make ready required.				*
Rte 947 / Smith's Landing Rd	1S	86.2	F				X						CMP shorten service taps for 2 services. No tel make ready required.		X		*
Rte 947 / Smith's Landing Rd	3	86.12	F				X						No make ready required. Guying required.				*
Rte 947 / Smith's Landing Rd	4	86.13	F				X						No make ready required. Guying required.				*
TS264 / West Bay Rd	549	85	F				X						No make ready required. Guying required.				*
TS264 / West Bay Rd	548 (547)	84	F				X						No make ready required.				*
TS264 / West Bay Rd	547	83	F				X						Tel lower 1 crw, 1 d/w 6". Guying required.	X		20A,19B	*
TS264 / West Bay Rd	547-1	83.1	F				X						Tel lower 1 d/w 12".	X		19A	*
TS264 / West Bay Rd	546	81	F				X						No make ready required.				*
TS264 / West Bay Rd	546-1	81.1	F				X						No make ready required.				*
TS264 / West Bay Rd	545	80	F				X						No make ready required. Guying required.				*
TS264 / West Bay Rd	544	77	F				X						Tel lower top d/w 6". Guying required.	X		19A	*
Rte 92 / Airport Rd	1	1	F				X						CMP place 18" U-guard on URD. Tel lower 2 d/w 12", 4 d/w 6" & refension. Guying required.	X	X	19A,(5)19B	*
Rte 92 / Airport Rd	2	2	F				X						CMP raise 3 services 12" & shorten taps. Tel raise 1 crw, 2 d/w 12". Guying required.	X	X	20A,(2)19B	*
Rte 92 / Airport Rd	2-1	2.1	F				X						No make ready required. Guying required.				*
Rte 92 / Airport Rd	NT	2.11	F										Customer owned meter pole.				*
Rte 92 / Airport Rd	2-2	2.2	F				X						CMP rpl 35'/40'. Tel transfer 1 crw, 4 d/w, 3 wire terms, 2 bsw. NO CHARGE. Noncompliant clearance, 28" from neutral, 16' driveway, >300' span. Guying required.	X	X		*

Location			Pole #	Attach		Ownership						Description of Work		FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks	Attach location see notes			
				Tel	El	Tel	El	Tel	El								
Rte 92 / Airport Rd	2-3	2.3	F				X			CMP rpl 35'/40' & anchor. Tel transfer 1 crw, 1 d/w, 2 wire terms, rpl 1 PA guy.	X	X	7A,17A,18B,21A,21B, 25A	*			
Rte 92 / Airport Rd	2-3	2.3	F				X			DDE(double deadend) second attachment.				*			
Rte 92 / Airport Rd	2-4	2.4	F				X			Tel lower top d/w 12". Guying required.	X		19A	*			
TS264 / West Bay Rd	543	76	F				X			No make ready required.				*			
TS264 / West Bay Rd	542	75	F				X			CMP shorten service taps 18". No tel make ready required.		X		*			
TS264 / West Bay Rd	541	74	F				X			No make ready required. Guying required.				*			
TS264 / West Bay Rd	541S	74.1	F				X			No make ready required. Guying required.				*			
TS264 / West Bay Rd	NT	74.1S							X	No Tel on pole. No make ready required.				*			
TS264 / West Bay Rd	541SS	74.11	F				X			Tel lower 1 d/w 12". Guying required.	X		19A	*			
TS264 / West Bay Rd	541-2	74.2	F				X			No make ready required. Guying required.				*			
TS264 / West Bay Rd	541-3	74.3	F				X			Tel lower 1 crw 12" & retension. Guying required.	X		20A	*			
TS264 / West Bay Rd	541-4	74.4	F				X			CMP raise service 12" & shorten taps. No Tel make ready required. Guying required.		X		*			
TS264 / West Bay Rd	540	73	F				X			No make ready required.				*			
TS264 / West Bay Rd	539	72	F				X			Tel raise 1 d/w 12". Guying required.	X		19A	*			
TS264 / West Bay Rd	539X	72.1	F				X			Tel lower 1 d/w 12".	X		19A	*			
TS264 / West Bay Rd	538	71	F				X			No make ready required. Guying required.				*			
TS264 / West Bay Rd	537	70	F				X			No make ready required. Guying required.				*			
TS264 / West Bay Rd	536	69	F				X			CMP shorten service taps. No tel make ready required.		X		*			
TS264 / West Bay Rd	535	68	F				X			No make ready required.				*			
TS264 / West Bay Rd	534	67	F				X			No make ready required. Guying required.				*			

Location			Pole #	Attach		Ownership										
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks	Attach location see notes		
				Tel	El	Tel	El	Tel	El							
TS264 / West Bay Rd	533	66	F				X			CMP rpl 35'/45' & anchor. Tel transfer 1 strand(2 ca), rpl 1 PA guy. Guying required.	X	X	7A,11A,25A	*		
TS264 / West Bay Rd	532	65	F				X			No make ready required.				*		
TS264 / West Bay Rd	531	64	F				X			CMP raise service 24" & shorten taps. No tel make ready required. Guying required.		X		*		
TS264 / West Bay Rd	530	63	F				X			CMP rpl 35'/40' & anchor. Tel transfer 1 strand(2 ca), 1 d/w, 1 wire term, rpl 1 PA guy.	X	X	7A,11A,17A,21A,25A	*		
TS264 / West Bay Rd	529S	62S					X			Tel lower 1 PP guy, 1 PA guy 12". Guying required.	X		10A,10B	*		
TS264 / West Bay Rd	529	62	F				X			Tel lower 1 PP guy 12". Guying required.	X		10A	*		
TS264 / West Bay Rd	528-1	61.1	F				X			No make ready required.				*		
TS264 / West Bay Rd	528	61	F				X			No make ready required.				*		
TS264 / West Bay Rd	527	60	F				X			No make ready required.				*		
TS264 / West Bay Rd	527-1	60.1	F				X			No make ready required.				*		
TS264 / West Bay Rd	527-2	60.2	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	526	NT	F					X		No CMP. Tel rpl 40'/40' & anchor. Tel transfer 1 strand(2 ca), rpl 1 PA guy. NO CHARGE. Noncompliant. Anchor pulled, pole leaning, cable tied to trees.		X		*		
TS264 / West Bay Rd	525	NT	F					X		No CMP. No make ready required.				*		
TS264 / West Bay Rd	524 1/2	53	F				X			No make ready required. Guying required.				*		
Rte 82 / off West Bay Rd	1	53.1	F				X			Tel lower 1 d/w 12". Guying required.	X		19A	*		
Rte 82 / off West Bay Rd	2	53.2	F				X			Tel lower 1 d/w 12". Guying required.	X		19A	*		
TS264 / West Bay Rd	524	52	F				X			Tel lower 1 strand(2 ca), 1 d/w, 1 wire term, 1 PA guy 18". Guying required.	X		10A,11A,19A,21A	*		
TS264 / West Bay Rd	523	51	F				X			No make ready required.				*		
TS264 / West Bay Rd	522	50	F				X			No make ready required. Guying required.				*		

Location			Pole #		Attach		Ownership						FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C PS	J.O.	J.U.	S.O.	Description of Work	Tel	El	Tel	El	Tel	El	Tel	El	
				Tel	El	Tel										
Rte 948 / off West Bay Rd TS264 P.522	1	50.1	F			X	CMP rpl 35'/40'. Tel transfer 2 crw, 1 d/w, 1 wire term.		X				X	X	18A,18B,17B,21A	*
Rte 948 / off West Bay Rd TS264 P.522	2	50.2	F			X	CMP raise 2 services 12" & shorten taps. No tel make ready required. Guying required.		X					X		*
TS264 / West Bay Rd	521	49	F			X	No make ready required.									*
TS264 / West Bay Rd	520	48	F			X	No make ready required.									*
TS264 / West Bay Rd	519	47	F			X	No make ready required. Guying required.									*
TS264 / West Bay Rd	519S	47S				X	No make ready required. Guying required.									*
TS264 / West Bay Rd	NT	47.1	F				No Tel on pole. No make ready required.					X				*
TS264 / West Bay Rd	518	46	F			X	Tel lower 1 strand(2 ca), 1 PP guy 6". Guying required.		X				X		10A,11A	*
TS264 / West Bay Rd	518S	46S				X	No make ready required. Guying required.									*
TS264 / West Bay Rd	517	45	F			X	No make ready required.									*
TS264 / West Bay Rd	516	44	F			X	New pole placed. Tel to transfer on another authority. No make ready required.									*
TS264 / West Bay Rd	NT	44.01					No pole found.									*
TS264 / West Bay Rd	NT	44.02					No pole found.									*
TS264 / West Bay Rd	NT	44.1	F			X	No Tel on pole. No make ready required. CMP submarine cable.					X				*
TS264 / West Bay Rd	NT	44.15					No Tel on pole. To be removed by CMP, beside new [P.44.1]					X				*
TS264 / West Bay Rd	NT	44.2	F				No Tel on pole. No make ready required. CMP submarine cable.					X				*
TS264 / West Bay Rd	515	43	F			X	Tel lower 1 d/w 12". Guying required.						X		19A	*
TS264 / West Bay Rd	515-1	43.1	F			X	No make ready required.									*
TS264 / West Bay Rd	NT	43.2					CMP transformer pad.									*
TS264 / West Bay Rd	515 1/2	43H	F			X	No make ready required.									*

Location			Pole #		Attach		Ownership									
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks	Attach location see notes		
				Tel	El	Tel	El	Tel	El							
TS264 / West Bay Rd	NT	NT								No pole found.				*		
TS264 / West Bay Rd	514	42	F				X			Tel lower 1 strand(2 ca), 1 d/w 24".	X		11A,19A	*		
TS264 / West Bay Rd	513	41	F				X			No make ready required.				*		
TS264 / West Bay Rd	512	40	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	511	39	F				X			CMP raise service 12" & shorten taps. Guying required.		X		*		
TS264 / West Bay Rd	510	38	F				X			CMP rpl 40'/45' & anchor. Tel transfer 1 strand(2 ca), 1 d/w, rpl 1 PA guy. Guying	X	X	7A,11A,17A,25A	*		
TS264 / West Bay Rd	509	37H	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	509S	37HS					X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	508 1/2	37	F				X			CMP raise 1 service 12" & shorten taps. No tel make ready required. Guying required.		X		*		
TS264 / West Bay Rd	508 1/2-1	37.1	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	508	36	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	508S	36S					X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	507	35	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	506	33	F				X			CMP raise 1 service 12" & shorten taps. No tel make ready required. Guying required.		X		*		
TS264 / West Bay Rd	NT	33.1								No pole found.				*		
TS264 / West Bay Rd	505	32	F				X			CMP rpl 35'/45'. Tel transfer 1 strand(2 ca), 1 d/w. NO CHARGE. Noncompliant clearance Tel 12" from CMP regulator.	X	X		*		
TS264 / West Bay Rd	504	31	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	504-1	31.1	F				X			No make ready required. Guying required.				*		
TS264 / West Bay Rd	503	30	F				X			No make ready required. Guying required.				*		

Location			Pole #	Attach		Ownership						Description of Work	FP	Others	Tasks	Attach location see notes
Tel Rte / Street Name	Tel	El	F/C	J.O.		J.U.		S.O.								
			PS	Tel	El	Tel	El	Tel	El	El						
TS264 / West Bay Rd	502	29	F				X				Tel lower 2 d/w, 1 wire term 12". Guying required.	X		19A,19B,21A	*	
TS264 / West Bay Rd	502-1	29.1	F				X				Tel lower 2 d/w, 1 wire term 12". Guying required.	X		19A,19B,21A	*	
TS264 / West Bay Rd	501	28	F				X				No make ready required.				*	
TS264 / West Bay Rd, Fairpoint CO	500	27	F				X				CMP shorten URD taps 12". No tel make ready required.	X			*	
Rte 3 / Ferry Rd	1	1	F				X				No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	1S	1S					X				No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	2	2	F				X				CMP raise service 12". No tel make ready required. Guying required.	X			*	
Rte 3 / Ferry Rd	2S	2S					X				No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	3	3	F				X				No make ready required.				*	
Rte 3 / Ferry Rd	4	4	F				X				Tel lower 2 strands(2 ca), 1 d/w, 1 PA guy 12".	X		10A,11A,11B,19A	*	
Rte 3 / Ferry Rd	4-1	4.1	F				X				No make ready required.				*	
Rte 3 / Ferry Rd	4S	4S					X				No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	5	5	F				X				No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	5-1	5.1	F				X				No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	NT	5S							X		No Tel on pole. No make ready required. Guying required.				*	
Rte 3 / Ferry Rd	6	6	F				X				CMP rpl 35'/40'. Tel transfer 2 strands(2 ca), 1 crw, rpl 1 PA guy. Guying required.	X	X	7A,11A,11B,18A,25A	*	
Rte 2641 / off Ferry Rd P.6[6]	1	6.1	F				X				Tel lower 1 crw 12". Guying required.	X		20A	*	
Rte 2641 / off Ferry Rd P.6[6]	2	6.2	F				X				Tel lower 1 crw 12". Guying required.	X		20A	*	
Rte 2641 / off Ferry Rd P.6[6]	3	6.3	F				X				CMP raise 1 service 12" & shorten taps. No tel make ready required. Guying required.	X			*	
Rte 3 / Ferry Rd	7	7	F				X				No make ready required.				*	

Location		Pole #	Attach		Ownership								Attach location see notes	
Tel Rte / Street Name	Tel	El	F/C PS	J.O.		J.U.		S.O.		Description of Work	FP	Others	Tasks	
				Tel	El	Tel	El	Tel	El					
Rte 3 / Ferry Rd	8	8	F				X			CMP rpl 40'/45'. Tel transfer 2 strands(2 ca), 1 mdw, rpl 2 PA guy. Guying required.	X	X	7A,7B,11A,11B,17A, 25A,25B	*
RP940 / Off Ferry Rd P.8[8]	1	8.1	F				X			Tel lower 2 d/w, 1 wire term 12". CMP raise service 12" & shorten taps.	X	X	19A,19B,21A	*
Totals				0	0	0	0	175	4	13	53	48		

Notes:

* Attach no closer than 40" below power attachment and 12" above telephone attachment.